ANNUAL REPAIR AND MAINTENANCE TO BUILDINGS AT DAANISH SCHOOL (BOYS), CHISHTIAN DISTRICT BAHAWALNAGAR (For the Year 2019-20)

DNIT/ B.O.Q

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
1	Distempering old surface one coat (roof & walls)	97997	%Sft	308.25	302076		
2	Distempering old surface two coats (roof & walls)	97997	%Sft	382.1	374447		
3	Scraping ordinary distemper, oil bound distemper or paint of wall	97997	%Sft	457	447846		
4	Painting old surface doors and windows any type one coat	25237	%Sft	539.25	136091		
5	Glazing with panes (16 oz to 18 oz) including cost of putty	544	PSft	65	35360		
6	Providing and fixing CP shower rose 1/2"x4"	48	Each	334.8	16070		
7	Providing and fixing gun metal peet / gate valve (screwed) 1 1/4" dia	35	Each	445.25	15584		
8	Providing and fixing CP mixing valve for wash hand basin sink or shower	50	Each	1560.05	78003		
9	Providing and fitting CP or brass oxidized swan neck cock 1/2" dia two way	55	Each	643.25	35379		
10	Providing and fixing 1/2" dia connection i/c check nuts etc plastic rubber connection	160	Each	49.7	7952		
11	Providing and fixing waste pipe of PVC 1 1/4" dia	155	Each	48	7440		
12	Providing and fitting plastic made low down flushing cistern 3 gallons capacity i/c bracket set, copper connection etc complete white	15	Each	1199.95	17999		
13	Supply & Errection of single core PVC insulated copper conductor cables, in prelaid PVC pipe / MS conduit / G.I. Pipe / wooden strip batten / wooden casing an capping / G.I. wire / trenches (rate for cables only) 250/440 volts, PVC insulated 7/0.029"	1200	PRft	15.95	19140		

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
14	Supply & Erection of single core PVC insulated copper conductor cables, in prelaid PVC pipe / MS conduit / G.I. Pipe / wooden strip batten / wooden casing an capping / G.I. wire / trenches (rate for cables only) 660/1100 volts, non-armoured cable 7/0.044"	290	PMtr	441	127890		
15	Rewiding of AC ceiling fan, capacitor type, including cost of wire, leatheride paper cotton tape, soldering, etc 56" sweep etc., 250-275 RPM	65	Each	1138.8	74022		
16	Supply and fitting of ball bearing of size 6201,6202 or 6203 for ceiling fans	130	Each	177.65	23095		
17	Supply & errection of switches 5 amp piano type	1800	Each	34.85	62730		
18	Supply & fitting capacitor 2.2 uF, for ceiling fans	125	Each	67.95	8494		
19	Supply & errection of bakelite button holder shade large size	300	Each	51.85	15555		
	Total				**1828626**		
	Add 16% PRA				**292581**		
	G.Total				**2121207**		
	Credit of Old Material				**5200**		
	Net Total				**2116007**		

Note : (i) B.O.Q is based on rates for 2nd Bi-annual 2019 i.e. from July Ist, 2019 to December 31st, 2019 (District Bahawalnagar)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2019 i.e. from July Ist, 2019 to December 31st, 2019 District Bahawalnagar shall be followed.

Rate quoted by the contractor _____ % Above/ Below on above BOQ rates(s).

Quantity Surveyor
PDS-CEA Lahore

Chief Quantity Evaluator
PDS-CEA Lahore

Assistant Manager Engg.
PDS-CEA Lahore

General Manager Engg.
PDS-CEA Lahore

ANNUAL REPAIR AND MAINTENANCE TO BUILDINGS AT DAANISH SCHOOL (GIRLS), CHISHTIAN DISTRICT BAHAWALNAGAR (For the Year 2019-20)

DNIT/ B.O.Q

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
1	Distempering old surface one coat (roof & walls)	42351	%Sft	308.25	130547		
2	Distempering old surface two coats (roof & walls)	42351	%Sft	382.1	161823		
3	Scraping ordinary distemper, oil bound distemper or paint of wall	42351	%Sft	457	193544		
4	Painting old surface doors and windows any type one coat	16247	%Sft	539.25	87612		
5	Glazing with panes (16 oz to 18 oz) including cost of putty	619	PSft	65	40235		
6	Providing and fixing CP shower rose 1/2"x4"	25	Each	334.8	8370		
7	Providing and fixing gun metal peet / gate valve (screwed) 1 1/4" dia	35	Each	445.25	15584		
8	Providing and fixing CP mixing valve for wash hand basin sink or shower	25	Each	1560.05	39001		
9	Providing and fitting CP or brass oxidized swan neck cock 1/2" dia two way	15	Each	643.25	9649		
10	Providing and fixing 1/2" dia connection i/c check nuts etc plastic rubber connection	130	Each	49.7	6461		
11	Providing and fixing waste pipe of PVC 1 1/4" dia	145	Each	48	6960		

Scanned by CamScanner

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
12	Providing and fitting plastic made low down flushing cistern 3 gallons capacity i/c bracket set, copper connection etc complete white	12	Each	1199.95	14399		
13	Supply & errection of switches 5 amp piano type	620	Each	34.85	21607		
14	Supply & fitting capacitor 2.2 uF, for ceiling fans	135	Each	67.95	9173		
15	Supply & errection of bakelite button holder shade large size	300	Each	51.85	15555		
	Total				**760520**		
	Add 16% PRA				**121684**		
	G.Total				**882204**		
	Credit of Old Material				**2500**		
	Net Total				**879704**		

Note : (i) B.O.Q is based on rates for 2nd Bi-annual 2019 i.e. from July Ist, 2019 to December 31st, 2019 (District Bahawalnagar)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2019 i.e. from July Ist, 2019 to December 31st, 2019 District Bahawalnagar shall be followed.

Rate quoted by the contractor _____ % Above/ Below on above BOQ rates(s).

Quantity Surveyor
PDS-CEA Lahore

Chief Quantity Evaluator
PDS-CEA Lahore

Assistant Manager Engg.
PDS-CEA Lahore

General Manager Engg.
PDS-CEA Lahore

Scanned by CamScanner