MAINTENANCE & REPAIR TO BUILDINGS AT CENTER OF EXCELLENCE BOYS DERA GHAZI KHAN

Package - 1 (Maintenance & Repair Works).

DNIT / BOQ

S .No	Description	Qty	Unit	Rate	Amount	Rate To be Quoted by the Contractor	
						Rate	Amount
Civil Work							
1	Scraping Distempring Ordinary distemper, oil bound distemper, or paint of wall	91391	%Sft	997.90	911986		
2	Preparing **one** coat of Distempering complete in all respect:- Old Surface	91391	%Sft	734.3	671080		
3	Preparing **two** coats of Distempering complete in all respect:- Old Surface	91391	%Sft	923.85	844311		
4	Preparing old surfaces Painting doors and windows, any type **single** Coats	10974	%Sft	1398.25	153443		
5	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect.b) old surface:	33079	%Sft	2456.00	812426		
Plumbing Work							
6	Providing and fitting glazed earthen ware water closet European type, excluding seat and cover:-earthen ware water closet white	5	Nos	14760.85	73804		
7	Providing and fixing, double seat and cover only.bakelite	5	Nos	1631.35	8157		
8	Providing and fitting plastic made low down flushing cistern 13.63 litre (3 gallons) capacity, including bracket set, copper connection, etc. complete.white	8	Nos	4574.2	36594		
9	Providing and fixing, chromium plated soap dish.	10	Nos	789.45	7895		

Quantity Surveyor
Punjab Danish Schools & Centres of Excellence Authority
Govt. Of The Punjab Lahore.

CamScanner

10	Providing and fixing chromium plated bib cock: ii) 1.5 cm (½"	30	Nos	1392.6	41778		
11	Providing and fixing chromium plated pillar-cock, heavy:-1.5 cm (½").	16	Nos	2712.6	43402		
12	Providing and fixing chromium plated stop cock, heavy:ii) 1.5 cm (½").	12	Nos	1392.6	16711		
13	Providing and fixing 1.5 cm (½") dia connection, including check nuts, etc.:- i) plastic rubber connection.	30	Nos	343.55	10307		
14	Providing & fixing Muslim Shower + dobule bib cock heavy.	11	Nos	4128.2	45410		
15	Providing and fitting glazed earthen ware wash hand basin 56x40 cm (22"x16") including bracket set, waste pipe and waste coupling, etc. white, with pedestal.	6	Nos	9600.3	57602		
Electrical Work							
16	Supply and erection of switches 5 Amp.						
	ii) Piano type	80	Each	98.3	7864		
17	Rewinding of A.C. ceiling fan, capacitor type, including cost of wire, leatheride paper cotton tape, soldering, etc. 1400 mm (56") sweep, 250-275 RPM.	24	Each	2690.35	64568		
18	Supply and erection of wall socket with 3 pin 5 Amp, shoe.	30	Each	200.15	6005		
19	Supply and erection of 3 pin switch and plug combined recessed type ii) 10/15 Amp	30	Each	207.65	6230		

Quantity Surveyor
Punjab Danish Schools & Centres of Excellence Authority
Govt. Of The Punjab Lahore.

CamScanner

20	Supply and fitting of capacitor 2.2 uF, for ceiling fans.	80	Each	258.9	20712		
21	Supply and erection of button holder i) bakelite large size	40	Each	75.85	3034		
Total					3,843,318		
Add 16 % PRA Tax					614,931		
D/d Old Material					(-) 13,800		
Grand Total					44,44,449.00		

Total 4458,249

Say 4.445 (m)

Note (i) B.O.Q is based on rates for 2nd Bi-annual 2023 i-e from 01-07-2023 to 31-12-2023 (District Dera Ghazi Khan)
(ii) In case of any ambiguity regarding rates M.R.S / Input Rate of finance department displayed on website for 2nd Bi-annual 2023 i-e from 01-07-2023 to 31-12-2023 (District Dera Ghazi Khan) shall be followed.

Sub-Engineer Civil
DS(B&G) D.G. Khan

Sub-Engineer Electrical
DS(B&G) D.G. Khan

Assistant Admin Officer
COE(B) D.G. Khan

Accounts Officer
COE D.G. Khan

Principal
COE (B) D.G. Khan

BOQ Approved for Rs: 4.445 (m).

Quantity Surveyor
Punjab Daanish Schools &
Centres of Excellence Authority
Govt. Of The Punjab Lahore.

Tariq Mahmood
Consultant
799-J2, Johar Town Lahore.

Deputy Manager (Engg)
Punjab Daanish Schools &
Centres of Excellence Authority
Govt. Of The Punjab Lahore

General Manager (Engg)
Punjab Daanish Schools &
Centres of Excellence Authority
Govt. Of The Punjab Lahore.

CamScanner

CONSTRUCTION OF MISSING BOUNDARY WALL AT CENTER OF EXCELLENCE BOYS DERA GHAZI KHAN

Package-2 (Missing Boundary Wall).

DNIT / BOQ

S .No	Description	Qty	Unit	Rate	Amount	Rate To be Quoted by the Contractor	
						Rate	Amount
Civil Work							
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain (30 m) and lift upto 5 ft. (1.5 m) in ordinary soil.	2100	%0Cft	13994.65	29389		
2	Cement concrete plain including placing compacting, finishing and curing complete (including screening and washing of stone aggregate):(i) Ratio 1: 4: 8	231	%Cft	29871.00	69002		
3	Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc and other structural members other than those mentioned in 5(a) (i) above not requiring form work (i.e. horizental shuttering) complete in all respects:- Type C (nominal mix 1: 2: 4).	386	Cft	501.80	193695		
4	Reinforced cement concrete in slab of raft/strip, foundation, base, slab of columns and retaining wall etc and footing, beams other structural members other than those mentioned in 6a(i) & (ii) above not requiring form work i.e horizontal shuttering complete in all respect. Type B (nominal mix 1: 1½: 3)	214	Cft	562.80	120439		
5	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60)	2656	% Kg	35144.45	933401		
6	Pacca brick work in cement, sand mortar foundation and plinth Ratio 1:6	607	% Cft	30999.35	188166		

Quantity Surveyor
Punjab Quaid an Schools &
Centres of Excellence Authority
Govt. Of The Punjab Lahore.

CamScanner

7	Pacca brick work other than building in cement, sand mortar Ratio 1:5	1093	% Cft	33193.45	362804		
8	1/2" thick Cement plaster (1:4) in ground floor upto 20' height	1600	% Sft	4015.20	64243		
9	Cement pointing struck joints, on walls, upto 20' (6.00 m) hiehgt ratio 1:2 i/c red oxide pigment	1350	% Sft	4394.50	59326		
10	Rehandling of earthwork Lead upto a single throw of Kassi, phaorah or shovel.	700	% Cft	3326.40	2328		
11	Providing and fixing anti climb high security galvanized razor cut wire having double sharp four U-shaped pointed 0.5 mm thick (22mmx15 mm barbs) spaced @ 33 mm c/c cladded over 2.5 mm dia high tensile Core wire making coil fencing of specified diameter @ 4" c/c fixed on 2'-3" high M/S angle iron post 1½"x1½"x3/16"embeded in base of PCC (1:2:4) (4"x4"x9") @ 4' apart i/c the cost of 2 No. bars 3/8" dia welded horizantally with angle iron posts , binding wire, painting of posts, etc. complete in all respects as pproved and directed by the Engineer incharge) 24 " diamete.	200	Rft	648.00	129600		
Total					**2152393**		
Add 5% PRA Tax					**107620**		
Grand Total					**2260013**		

Say Rs 2.260(m)

Note (i) B.O.Q is based on rates for 2nd Bi-annual 2023 i-e from 01-07-2023 to 31-12-2023 (District Dera Ghazi Khan)
(ii) In case of any ambiguity regarding rates M.R.S / Input Rate of finance department displayed on website for 2nd Bi-annual 2023 i-e from 01-07-2023 to 31-12-2023 (District Dera Ghazi Khan) shall be followed.

Sub-Engineer Civil
DS(B&G) D.G. Khan

Sub-Engineer Electrical
DS(B&G) D.G. Khan

Assistant Admin Officer
COE(B) D.G. Khan

Accounts Officer
COE D.G. Khan

Principal
COE (B) D.G. Khan

BOQ Approved for Rs 2.260(m)

District Surveyor
Punjab Daanish Schools & Centres of Excellence Authority
Govt. Of The Punjab Lahore.

Tariq Mahmood
Consultant
709-J2, Johar Town Lahore.

Deputy Manager (Engg)
Punjab Daanish Schools & Centres of Excellence Authority
Govt. Of The Punjab Lahore

General Manager (Engg)
Punjab Daanish Schools & Centres of Excellence Authority
Govt. Of The Punjab Lahore.

CamScanner

MAINTENANCE & REPAIR TO BUILDINGS AT CENTER OF EXCELLENCE GIRLS DERA GHAZI KHAN

DNIT / BOQ

S .No	Description	Qty	Unit	Rate	Amount	Rate To be Quoted by the Contractor	
						Rate	Amount
Civil Work							
1	Removing of Doors	10	Nos	576.2	5762		
2	P/F 1-1/2" thick solid flush door comprising of 2.5 mm thick Deodar/Ash/Oak ply with grooves , compressed over 2.5 mm thick commercial ply over 1" thick packing wood in style and rails under proper pressure i/c the cost of nails, tower bolt , handles, glue, sawing charges and lacquar polishing to show the grains of ply properly, sand papering and 3/8" thick matching wooden lipping as approved and directed by the Engineer Incharge.	245	Sft	1059.5	259578		
3	Scraping Distempring Ordinary distemper, oil bound distemper, or paint of wall	66383	%Sft	997.90	662436		
4	Preparing **one** coat of Distempering complete in all respect:- Old Surface	63383	%Sft	734.3	465421		
5	Preparing **two** coats of Distempering complete in all respect:- Old Surface	63383	%Sft	923.85	585564		
6	Preparing old surfaces Painting doors and windows, any type **single** Coats	6504	%Sft	1398.25	90946		
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect.b) old surface:	21618	%Sft	2456.00	530926		
Plumbing Work							
8	Providing and fitting glazed earthen ware water closet European type, excluding seat and cover:-earthen ware water closet white	6	Nos	14760.35	88565		
9	Providing and fixing, double seat and cover only.bakelite	6	Nos	1631.35	9788		
10	Providing and fitting plastic made low down flushing cistern 13.63 litre (3 gallons) capacity, including bracket set, copper connection, etc. complete.white	10	Nos	4574.2	45742		
11	Providing and fixing, chromium plated soap dish.	10	Nos	789.45	7895		
12	Providing and fixing chromium plated bib cock: ii) 1.5 cm (½"	30	Nos	1392.6	41778		

Quantity Surveyor
PWD-EA
Government of Punjab

13	Providing and fixing chromium plated pillar-cock, heavy:-1.5 cm (½").	16	Nos	2712.6	43402		
14	Providing and fixing chromium plated stop cock, heavy:ii) 1.5 cm (½").	12	Nos	1392.6	16711		
15	Providing and fixing 1.5 cm (½") dia connection, including check nuts, etc.:- i) plastic rubber connection.	30	Nos	343.55	10307		
16	Providing & fixing Muslim Shower + dobule bib cock heavy.	12	Nos	4128.2	49538		
17	Providing and fitting glazed earthen ware wash hand basin 56x40 cm (22"x16") including bracket set, waste pipe and waste coupling, etc. white, with pedestal.	6	Nos	9600.3	57602		
Electrical Work							
18	Supply and erection of switches 5 Amp.						
	ii) Piano type	30	Each	49.35	1481		
19	Rewinding of A.C. ceiling fan, capacitor type, including cost of wire, leatheride paper cotton tape, soldering, etc. 1400 mm (56") sweep, 250-275 RPM.	15	Each	2690.45	40357		
20	Supply and fitting of capacitor 2.2 uF, for ceiling fans.	50	Each	258.9	12945		
BOQ Approved for Rs 3.481 (m)	**Total**				**3,026,742**	✓	
	Add 16 % PRA Tax				484,279		
	D/d Old Material				-29680		
	Grand Total -B				**3,481,341**	✗	

Total

Say Rs: 3.481 (m)

General Manager (Engg)
Punjab Daanish Schools &
Centres of Excellence Authority
Govt. Of The Punjab Lahore

Note (i) B.O.Q is based on rates for 2nd Bi-annual 2023 i-e from 01-07-2023 to 31-12-2023 (District Dera Ghazi Khan)
(ii) In case of any ambiguity regarding rates M.R.S / Input Rate of finance department displayed on website for 2nd Bi-annual 2023 i-e from 01-07-2023 to 31-12-2023 (District Dera Ghazi Khan) shall be followed.

DNIT Approved for Rs.3.48/M

Sub-Engineer Civil
DS(B&G) D.G. Khan

Sub-Engineer Electrical
DS(B&G) D.G. Khan

Assistant Admin Officer
COE(G) D.G. Khan

Accounts Officer
COE D.G. Khan

Principal
COE (G) D.G. Khan
6/10/2023

Quantity Surveyor
PD&E CEA
Government of Punjab

Tariq Mahmood
Consultant
799-J2, Johar Town Lahore.

Deputy Manager (Engg)
Punjab Daanish Schools &
Centres of Excellence Authority
Govt. Of The Punjab Lahore