P/F OF TUFF PAVERS IN PATIO OF HOSTELS AT DAANISH SCHOOL (BOYS) JAND DISTRICT ATTOCK

DNIT/ B.O.Q

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
1	Regular excavation dressed i/c disposal off surplus earth up to 300 ft.	3412	%0Cft	3659.40	12486		
2	Providing, laying, watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) guage mixed with 25% sand for floor foundation, complete in all respects.	2252	%Cft	5275.25	118799		
3	Providing and laying Tuff pavers having 7000 PSI, crushing strength of approved manufacture over 2" to 3" sand cushion/grouting with sand in joints i/c finishing to require slope. Complete in all respect. (50% Grey / 50% Coloured	6825	PSft	103.95	709459		
	Total				**840744**		
	Add 5 % PRA Tax				**42037**		
	Grand Total				**882781**		
	Say				**0.883(M)**		

Note (i) B.O.Q is based on rates for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 (District Attock)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 shall be followed.

Quantity Surveyor
PDS-CEA Lahore

Cheif Quantity Evaluator
PDS-CEA Lahore

Deputy Manager (Engg)
PDS-CEA Lahore

MALALA YOUSAFZAI DAANISH SCHOOL (BOYS) JAND, ATTOCK
SEEN BY
PRINCIPAL
ADMIN OFFICER
DEPUTY HEAD
ACCOUNT OFFICER
HEAD CLERK
DIARY NO
DATE

Malala Yousafzai Daanish School
Girls Campus Jand: Attock

P/F OF TUFF PAVERS IN PATIO OF HOSTELS AT DAANISH SCHOOL (GIRLS) JAND DISTRICT ATTOCK

DNIT/ B.O.Q

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
1	Regular excavation dressed i/c disposal off surplus earth up to 300 ft.	3412	%0Cft	3659.40	12486		
2	Providing, laying, watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) guage mixed with 25% sand for floor foundation, complete in all respects.	2252	%Cft	5275.25	118799		
3	Providing and laying Tuff pavers having 7000 PSI, crushing strength of approved manufacture over 2" to 3" sand cushion/grouting with sand in joints i/c finishing to require slope. Complete in all respect. (50% Grey / 50% Coloured	6825	PSft	103.95	709459		
	Total				**840744**		
	Add 5 % PRA Tax				**42037**		
	Grand Total				**882781**		
	Say				**0.883(M)**		

Note : (i) B.O.Q is based on rates for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 (District Attock)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 shall be followed.

Quantity Surveyor
PDS-CEA Lahore

Cheif Quantity Evaluator
PDS-CEA Lahore

Deputy Manager (Engg)
PDS-CEA Lahore

P/F GRATING ON SURFACE WATER CHANNELS AT DAANISH SCHOOL (BOYS) JAND DISTRICT ATTOCK

DNIT/ B.O.Q

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
1	Making and fixing grating in opening including fixing at site with angle iron frame 1 1/2"x1 1/2"x3/8" and 3/4"x3/4" square bars 2" c/c	1280	P.Sft	922.00	1180160		
2	Preparing surface and painting guard bars gates of iron bars, gratings, railing (including standards braces, etc.,) and in similar open work.	1280	%Sft	1165.85	14923		
	Total				**1195083**		
	Add 5 % PRA Tax				**59754**		
	Grand Total				**1254837**		
	Say				**1.255 (M)**		

Note : (i) B.O.Q is based on rates for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 (District Attock)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 shall be followed.

Quantity Surveyor
PDS-CEA Lahore

Cheif Quantity Evaluator
PDS-CEA Lahore

Deputy Manager (Engg)
PDS-CEA Lahore

P/F GRATING ON SURFACE WATER CHANNELS AT DAANISH SCHOOL (GIRLS) JAND DISTRICT ATTOCK

DNIT/ B.O.Q

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
1	Making and fixing grating in opening including fixing at site with angle iron frame 1 1/2"x1 1/2"x3/8" and 3/4"x3/4" square bars 2" c/c	1408	P.Sft	922.00	1298176		
2	Preparing surface and painting guard bars gates of iron bars, gratings, railing (including standards braces, etc.,) and in similar open work.	1408	%Sft	1165.85	16415		
	Total				**1314591**	✓	
	Add 5 % PRA Tax				**65730**	✓	
	Grand Total				**1380321**	✓	
	Say				**1.380 (M)**	✓	

Note : (i) B.O.Q is based on rates for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 (District Attock)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 shall be followed.

SCHOOL (BOYS) JAND ATTOCK
SEEN BY
PRINCIPAL
ADMN OFFICER
DEPUTY HEAD
ACCOUNT OFFICER
HEAD CLERK
DIARY NO
DATE 21/1/21

Quantity Surveyor
PDS-CEA Lahore

Cheif Quantity Evaluator
PDS-CEA Lahore

Deputy Manager (Engg)
PDS-CEA Lahore

Principal Girls: (F.P.P)

CONSTRUCTION OF CANTEENS AT DAANISH SCHOOL (BOYS & GIRLS) JAND DISTRICT ATTOCK (REVISED)

DNIT/ B.O.Q

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
	A - Standardized Items						
1	Excavation in bundation of building bridges and other structures, including degbelling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain(30m)and lift upto 5 ft (1.5m) in ordinary soil.	3498	%oCft	7492.30	26208		
2	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio (1:4:8)	190	%Cft	17250.40	32776		
3	Dry rammed brick or stone ballast, 1½" to 2"(40 mm to 50 mm) gauge.	196	%Cft	4909.10	9622		
4	Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc and other structural members other than those mentioned in 5(a) (i) above not requiring form work (i.e. horizental shuttering) complete in all respects:- Ratio 1:2:4	380	PCft	257.85	97983		
5	Pacca brick work in 1:6 cement sand morter in foundation and plinth.	1512	%Cft	20896.15	315950		
6	Providing and laying DPC cement cncrete1:2:4 with one coats of bitumen blinded with sand and p-theen sheet 1- 1/2" thick.	446	%Sft	4936.75	22018		
7	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating:- (a) with one coat of bitumen and one coat of polythene sheet 500 gauge:Ratio 1:3, ½ " thick (13 mm)	352	%Sft	3410.05	12003		

MALALA YOUSAFZAI DAANISH SCHOOL (BOYS) JAND. ATTOCK
SEEN BY
PRINCIPAL
ADMIN OFFICER
DEPUTY HEAD
ACCOUNT OFFICER
HEAD CLERK
DIARY NO
DATE 29/11/21

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
8	Pacca brick work in ground floor in 1:6 cement sand morter.	1778	%Cft	22409.95	398449		
9	Reinforced cement concrete: in roof slab, columns lintels, girders and other structural members laid in situ or pre cast laid in position, or pre stressed members cast in situ, complete in all respect.Ratio 1:2:4	774	PCft	362.70	280730		
10	Fabricatin of mild steel reinforcement for cement concrete including cutting, bending,laying in position making joints and fastening I/c cost of steel reinforcement (also including removal of rust from bars) deformed bar. Grade -60	5948	%Kg	15809.75	940364		
11	3/8" thick cement plaster 1:3 upto 20' height.	1224	%Sft	2339.50	28635		
12	1/2" thick Cement plaster 1:4 upto 20' (6.00 m) height:-	4004	%Sft	2054.75	82272		
13	Cement pointing struck joints on walls upto 20' heighy ratio 1:2.Extra cost for labour and material for red oxide pigment in cement pointing to match the colour of brick.	2356	%Sft	2674.40	63009		
14	Providing and fixing 1½" (40mm) thick solid flush door shutter(Approved Factory Manufactured) with commercial ply (5 mm thick) on both sides double pressed and deodar wood lipping 1½"x3/8" (40mm x 10mm) around shutter including chromium plated fitting, iron hinges with aluminium kick plate 22 SWG on both sides & finger plate complete in all respect i/c M.S Chokhat of 1-1/2"x1-1/2"x1/4" angle iron welded with 2"x1/4" flat iron complete.	190	PSft	777.80	147782		
15	Providing and fixing sliding bolt to doors iron sliding bolt, 12" (300 mm) long	8	Each	369.70	2958		

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
16	Providing and fixing steel windows using M.S. sheet (16 SWG) moulded tubular pipe 1½"x1½" (40x40mm) for frame and 1¼"x1¼" (30x30mm) for leaves including M.S. square bars ¼"x¼" (6x6 mm) welded around each panel of frame, 5 mm thick glass panes fixed with double M.S. square tubular pipe 3/8"x3/8" (10x10mm) (22 SWG) beading with U' shaped rubber lining, brass fitting, holdfast, including painting three coats complete in all respects. a) For openable panels fixed with wire gauze 24 SWG, 12x12 mesh and glass	192	PSft	391.55	75178		
17	Preparing surface and painting of doors and windows any type (including edges):- 3coats	364	%Sft	1713.90	6239		
18	Wite washing three coats on new surface.	1226	%Sft	396.40	4860		
19	Distempering new surface three coats	3654	%Sft	777.20	28399		
20	Filling, watering and ramming earth under floors:- with surplus earth from foundation, etc	2166	%oCft	3583.55	7762		
21	Filling, watering and ramming earth under floors:- with with new earth excavated from outside, lead upto one chain (30 m)	210	%oCft	7193.30	1511		
22	S/filling sand under floor or plugging in well.	516	%Cft	1856.10	9577		
23	Providing, laying, watering and ramming brick ballast 1½" to 2"(40 mm to 50 mm) gauge mixed with 25% sand, for floor foundation, complete in all respects.	516	%Cft	5275.25	27220		
24	1½"(40 mm) thick mosaic flooring, consisting of ½ "(13 mm) mosaic topping of one part of cement and marblepowder in the ratio of 3:1 and two parts of marble chips,laid over 1"(25 mm) thick floor of 1:2:4 cement concrete,including rubbing and polishing complete with finishing :- (a) using grey cement	1192	%Sft	11612.30	138419		

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
25	Providing and laying topping of cement concrete 1:2:4, ncluding surface finishing and dividing in panels:- 1-1/2" thick	656	%Sft	4116.60	27005		
26	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):1:2:4	13	%Cft	21623.20	2811		
27	Laying floor of approved white glazed tile ¼" (6 mm) thick in white cement 1:2 over ¾" (20mm) thick cement mortar 1:2, complete.	34	%Sft	15305.05	5204		
28	White glazed tile (6"x6"x¼") (6 mm) thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" (20mm) thick, including finishing.	118	%Sft	16753.10	19769		
29	Providing and Laying Marble stirips 6mm.	1108	PRft	7.90	8753		
30	Cast iron rain water downpipe fixed in position, excluding heads and shoes, but including painting and clamps, etc: a) 3" dia (100 mm) cast iron down pipe.	48	PRft	205.35	9857		
31	Shoes, bends or offsets for cast iron rain water down pipe, including fixing and painting.	4	Each	336.70	1347		
32	Rain water down pipe cast iron head fixed in place, including cost of clamp holdfast and painting.	4	Each	575.95	2304		
33	Single layer of tiles 9"x(4.5)"x(1.5)" laid 4"earth and 1"mud plasted without qouted with cement sand in 1:3 on top of RCC roof slab provided with 34 Lbs: bitumen coating sand blinded i/c one layer of polythene sheet 500gm.	1236	%Sft	6992.15	86423		
34	Khuras on roof 2'x2'x6" (600 x 600 x 150 mm)	4	Each	534.65	2139		
35	Cement concrete brick or stone ballast 1 1/2" to 2" guage in foundation & plinth 1:4:8	112	%Cft	13587.95	15219		
36	Pacca brick work cement sand mortar other than building upto 10' heigh ratio 1:6	192	%Cft	21637.35	41544		

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
37	Rehandling of earthwork lead upto a single throw of kassi phaorah or shovel	121	%oCft	1776.70	215		
38	Providing and laying tuff pavers, having 7000 PSI, crushing strength of approved manufacturer, over 2" to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope. Complete in all respect (50% Grey/50% coloured) 50-mm thick.	800	PSft	92.90	74320		
39	Earthwork excavation in open cutting for sewers and manhole as shown in drawings including shuttering and timbering, dressing to correct section and dimensions according to emplates and levels and removing surface water in all types of soil except shingle, gravel and rock 0ft to 7ft depth	1802	%oCft	6221.15	11211		
40	Excavation of trenches in all kinds of soil except cutting rock for water supply pipelinesupto 5ft depth from ground level including trimming dressing sides levelling the beds of trenches to correct grade and cutting pits for joints etc complete in all respect.	585	%oCft	5340.20	3124		
41	Providing and lying RCC pipe moulded with cement concrete 1:1 1/2:3 with spigot socket or collar joint, etc including cost of reinforcement conforming to BS 5911 part I 1981 Class "L" including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing, cutting pipes where necessary finishing and testing etc., complete 225mm 9" i/d	220	PRft	365.60	80432		
42	Providing and fixing 1 1/4"x1 1/4"x3/16" angle iron step in manhole chambers, including carriage and setting the same in work to correct lines and levels	12	Each	333.35	4000		

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
43	Extra for making finishing and benching floor work in manhole chamber, with 1/8" thick cement finish	20	%Sft	1816.40	363		
44	Providing and fixing 3" thick RCC manhole cover with 3"x3"x1/4" angle iron frame 22" i/d as per standard drawing STD/PD No. 7 of 1977 complete in all respect.	4	Each	7114.85	28459		
45	1/2" thick cement plaster 1:4 upto 20 height i/c bitumen coating to plastered or cement concrete surface 20 lbs per 100 Sft	35	%Sft	3210.90	1124		
	Plumbing Works						
46	Providing and fixing stainless steel sink with drain board, size 120x60 cm (48"x24") including bracket set, waste pipe and waste coupling.	2	Each	4585.75	9172		
47	Providing and fitting glazed earthen ware wash hand basin 56x40 cm (22"x16") including bracket set, waste pipe and waste coupling, etc.white, with pedestal	2	Each	2697.90	5396		
48	Providing and fitting glazed earthen ware water closet, squatter type (Orisa pattern), combined with foot rest. i) white	2	Each	1274.20	2548		
49	Providing and fitting "P" trap:-10 cm (4") glazed.	6	Each	480.60	2884		
50	Providing and fitting plastic made low down flushing cistern 1363 litre (3 gallons) capacity, including bracket set, copper connection, etc. complete. i) white	2	Each	2153.75	4308		
51	Providing and fitting 10 cm (4") gully trap, including cement concrete, cost of PVC grating 15x15 cm (6"x6") and masonry chamber 30x30 cm (12"x12").	4	Each	733.35	2933		
52	Providing and fixing, floor trap of cast iron, including concrete chamber all round, and C.I. grating:-10x5 cm (4"x2")	6	Each	417.30	2504		
53	Providing and fixing chromium plated bib cock:1.5 cm (½")	4	Each	339.30	1357		

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
54	Providing and fitting, chromium plated or brass oxidised, swan neck cock 15 mm (½") dia. i) single way	4	Each	381.30	1525		
55	Providing and fixing, chromium plated soap dish.	4	Each	198.05	792		
56	Providing and fixing, chromium plated towel rail:-	2	Each	305.35	611		
57	Providing and fixing looking glass 55x40 cm (22"x16") size, and 5 mm thick, first quality.	2	Each	396.55	793		
58	Providing and fixing chromium plated tee stop cock 15mm (½")	6	Each	459.30	2756		
	E.I. Portion						
59	Supply & errection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries, and repairing surface etc complete with all specials						
i	25mm dia	1000	PRft	54.65	54650		
ii	32mm dia	190	PRft	67.95	12911		
60	Supply & errection of single core PVC insulated copper conductor cables, in prelaid PVC pipe/MS conduit/G.I. Pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) 250/440 volts						
i	3/0.029"	1800	PRft	12.50	22500		
ii	7/0.029"	700	PRft	16.80	11760		
iii	7/0.036"	600	PRft	23.90	14340		
iv	Twin Core 7/0.044"	60	PRft	70.50	4230		
v	Twin Core 7/0.064"	130	PRft	137.20	17836		

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
61	Supply & errection of MS sheet box of 16 SWG 4" deep with 4.75mm thick bakelite sheet top, for recessed wiring including making holes for regulators, switches plug etc.,						
i	4"x4"	22	Each	169.25	3724		
ii	7"x4"	24	Each	236.80	5683		
62	Supply & errection of ceiling rose, bakelite	8	Each	41.60	333		
63	Supply & errection of piano type switches 5 amp.	50	Each	38.30	1915		
64	Supply & errection of 3 pin switch & plug combined recessed type						
i	5 Amp	16	Each	75.45	1207		
ii	10-15 Amp	8	Each	101.65	813		
65	Supply & errection of button holder bakelite large size	28	Each	32.80	918		
66	Supply & errection of 3/8" dia MS bar fan hook, placed at the time of casting of slab.	10	Each	42.95	430		
67	Earthing of iron clad / aluminum switches, etc with G.I. wire No. 8 SWG in G.I. Pipe 15mm (1/2" dia) recessed or on surface of wall and floor complete with 1.5 meter long G.I. Pipe 50mm 2" dia with reducing socket 4 to 5 meter long ground level and 2 meter away from building plinth	2	Each	5743.00	11486		
68	Providing and fixing MS iron box for housing main switches, made of 1.5mm thick MS sheet with locking arrangement including painting 24"x14"x6	2	Each	3001.30	6003		
	N.S. Items						
69	Supply, installation of 56" dia ceiing fan made with 99% pure copper windings of approved firm PAK, Royal, GFC or equivalent as approved by Engineer Incharge.	10	Each	4685.00	46850		

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
70	P/F exhaust fan 12" dia plastic body (double action) GFC/PAK Fan/Royal Fan or equivalent as approved by Engineer Incharge.) i/c louvered shutter i/c making electric connection upto 1-meter length with existing point complete in all respect.	8	Each	2100.00	16800		
71	Supply installation of louver bracket fan 18" (GFC/PAK Fan/Royal Fan or equivalent as pproved by the Engineer Incharge i/c making connection upto one meter length with existing point.	4	Each	3425.00	13700		
72	Providing and fixing fan dimmer with switch of approved firm fixed on existing back box with all associated accessories as approved by the Engineer Incharge.	10	Each	160.00	1600		
73	Supply installation of LED bulb 12 W PHILIPS or as approved by the Engineer Incharge.	28	Each	290.00	8120		
74	P/F MS cabinet consisting of 16 SWG MS sheet duly powder coated with glass plated leaf i/c locking arrangement with necessary fittings size 18"x24" and 6" to 9" deep complete in all respect with following components: MCCB 50 Amp DPN, 6KA Terasaki Japan, Legrand France, GE, USA or equivalent 1-No. P/F MCB 6 to 20 Amp SP, 2.5 KA Terasaki Japan, Legrand Frand, GE, USA or equivalent 10-No P/F phase indicators 1-No P/F Ampere Meter 0-100 Amp (imported Newzeland or equivalent) 1-No P/F Volt Meter 0-500 Amp (imported Newzeland or equivalent) 1-No P/F Thimbles / Wire / Accessories / Links etc., 1-Job P/F current transformers 1-No	2	Each	15700.00	31400		
75	Supply & installation of MCB 50-Amp DPN, 6KA Terasaki Japan, Legerand France, GE, USA or equivalent with check nuts and thimbles etc as approved by the Engineer Incharge	2	Each	2370.00	4740		

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
76	Supply and instalation of PPRC Pipe of approved firm with fusion of threaded joints complete in all respect i/c specials as approved by the Engineer Incharge						
i	20mm	120	PRft	48.00	5760		
ii	25mm	40	PRft	56.00	2240		
iii	32mm	160	PRft	79.00	12640		
77	Providing and Fixing PPRC Stop Cock of approved firm as approved by the Engineer Incharge 32mm.	4	Each	460.00	1840		
78	Providing and Fitting UPVC Soil Pipe of approved firm as approved by the Engineer Incharge i/c specials complete in all respect.						
i	3" dia	40	PRft	135.00	5400		
ii	4" dia	20	PRft	171.00	3420		
	Total				**3548369**		
	Add 5% PRA				**177418**		
	G.Total				**3725787**		
	Say				**3.725 (M)**		

Note (i) B.O.Q is based on rates for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 (District DG.Khan)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 shall be followed.

Quantity Surveyor
PDS-CEA Lahore

Cheif Quantity Evaluator
PDS-CEA Lahore

Deputy Manager (Engg)
PDS-CEA Lahore

04/02/21

CONSTRUCTION OF BASKETBALL COURT AT DAANISH SCHOOL (GIRLS) JAND DISTRICT ATTOCK

DNIT/ B.O.Q

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
	CIVIL WORK						
1	Excavation in foundation of building bridges & other structures, including degbelling, dressing re-filling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5ft in hard soil or soft murum	583	%oCft	7492.30	4368		
2	Dry rammed brick or stone ballast 1 1/2" to 2" quage	2055	%Cft	4909.10	100882		
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6	205	%Cft	20896.15	42837		
4	Supplying and filling sand under floor or plugging in wells	1822	%Cft	1856.10	33818		
5	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels size 1 1/2"x1/4"	3039	PRft	7.90	24008		
6	Providing and lying topping of cement concrete 1:2:4 including surface finishing and dividing in panels 3" thick	5700	%Sft	6794.35	387278		
7	Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone agreegate) ratio (1:2:4)	24	%Cft	21623.20	5190		

MALALA YOUSAFZAI DAANISH SCHOOL (BOYS) JAND, ATTOCK
SEEN BY
PRINCIPAL
ADMIN OFFICER
DEPUTY HEAD
ACCOUNT OFFICER
HEAD CLERK
DIARY NO
DATE 1/2/21

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
8	P/F BasketBall Pole consisting of M.S Pipe 8" dia 3/16" thick 18'-0", 3'-0" below NSL and 15'-0" above NSL, i/c Deodar Wood board 1½" thick size 6'x4', i/c M.S bar 1/2" dia ring of standard size with M.S Plate 1/4" thick i/c screws, nails and painting 3 coats complete in all respect and as approved by the Engineer Incharge	2	Each	38822.00	77644		
	Total				**676025**		
	Add 5% PRA				**33801**		
	G.Total				**709826**		
	Say				**0.709 (M)**		

Note : (i) B.O.Q is based on rates for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 (District Attock)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 shall be followed.

Quantity Surveyor
PDS-CEA Lahore

Chief Quantity Evaluator
PDS-CEA Lahore

26/1/2021.
Deputy Manager (Engg.)
PDS-CEA Lahore

09/2/21