ANNUAL REPAIR & MAINTENANCE TO BUILDINGS AT CENTRE OF EXCELLENCE (BOYS) GOVT. HIGH SCHOOL NO. 1 D.G.KHAN

DNIT/ B.O.Q

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
1	Scraping distempering ordinary distemper, oil bound distemper or paint of wall	86564	%Sft	469.65	406547		
2	Distempering on old surface						
i	One Coat	128858	%Sft	311.65	401586		
ii	Two Coats	128858	%Sft	387.50	499325		
3	Painting to doors and windows any type one coat on old surface	15854	% Sft	549.70	87149		
4	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect on old surface.	42188	% Sft	742.90	313415		
	ELECTRICAL WORK						
5	Supply & Errection of switches 5 amp piano type	139	Each	35.40	4921		
6	Supply & errection of button holder bakelite large size	14	Each	30.45	426		
7	Supply & fitting of capacitor 2.2 uF for ceiling fans	150	Each	69.25	10388		
8	Rewinding of A.C. ceiling fan capacitor type, including cost of the credit of out turn of dismantled wire, leatheride paper cotton tape soldering etc 1400mm 56" sweep 250-275 RPM	14	Each	1152.65	16137		

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
	NS ITEMS						
9	Supply & errection of fan dimmer complete in all respect as approved by the Engineer Incharge	61	Each	170.00	10370		
	Total				**1750264**		
	Add 16% PRA				**280042**		
	G.Total				**2030306**		
	Credit of Old Material			(-)	**2170**		
	Net Total				**2028136**		
	Say				**2.028 Mn**		

Note : (i) B.O.Q is based on rates for 2nd Bi-annual 2019 i.e. from July Ist, 2019 to December 31st, 2019 (District D.G.Khan)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2019 i.e. from July Ist, 2019 to December 31st, 2019 shall be followed.

Rate quoted by the contractor _____ % Above/ Below on above BOQ rates(s).

Quantity Surveyor
PDS-CEA Lahore

Chief Quantity Evaluator
PDS-CEA Lahore

Deputy Manager Engg.
PDS-CEA Lahore

Manager Engg.
PDS-CEA Lahore

General Manager Engg.
PDS-CEA Lahore