ANNUAL REPAIR AND MAINTENANCE TO BUILDINGS AT DAANISH SCHOOL (BOYS), D.G.KHAN (For the Year 2019-20)

DNIT/ B.O.Q

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
	ACADEMIC BLOCK & HOSTEL BUILDING						
1	Distempering one coat on old surface	208065	% Sft	311.65	648435		
2	Painting to doors and windows any type one coat on old surface	10220	% Sft	549.70	56179		
3	Preparing surface and painting with emulsion paint one coat	40665	% Sft	762.40	310030		
4	Removing of doors	22	Each	251.05	5523		
5	Scraping distempering ordinary distemper, oil bound distemper or paint of wall	14740	%Sft	469.65	69226		
6	Providing and fixing 1 1/2" thick solid flush door shutter (approved factory manufactured) with commercial ply 5mm thick on both sides double pressed and deodar wood lipping 1 1/2"x3/8" around shutter including CP fitting iron hinges with aluminum kick plate 22 SWG on both sides & finger plate complete in all respect	322	PSft	365.25	117611		
	ELECTRICAL WORK						
1	Supply & Errection of switches 5 amp piano type	35	Each	35.40	1239		
2	Supply & Errection of 3 pin socket 10-15 amp with shoe open type	12	Each	50.70	608		
3	Rewinding of A.C. ceiling fan capacitor type, including cost of the credit of out turn of dismantled wire, leatheride paper cotton tape soldering etc 1400mm 56" sweep 250-275 RPM	27	Each	1152.65	31122		
4	Supply & fitting of capacitor 2.2 uF, for ceiling fans	45	Each	69.25	3116		

Scanned with CamScanner

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
5	Supply & Errection of single core PVC insulated copper conductor cables, in prelaid PVC pipe / MS conduit / GI Pipe / wooden strip batten / wooden casing and capping / G.I. Wire / trenches (rate for cables only)						
i	3/0.029"	590	PRft	11.85	6992		
ii	7/0.029"	295	PRft	16.15	4764		
	PLUMBING WORK						
1	Providing and fixing chromium plated pillar-cock, heavy:ii) 1.5 cm (½")	8	Each	545.70	4366		
2	Providing and fixing chromium plated shower rose:-i) 1.5x10 cm (½"x4")	58	Each	335.70	19471		
3	Providing and fixing, chromium plated waste coupling:-i) 3 cm (1¼")	18	Each	128.55	2314		
4	Providing and fixing, waste pipe of PVC:-ii) 4 cm (1½")	18	Each	54.70	985		
5	Providing and fixing Glass shelf 60x13 cm (24"x5") with 5mm thick glass with chromium plated brackets & railing complete in all respect.	30	Each	393.15	11795		
6	Providing and fixing, chromium plated towel rail:-i) 60 cm (24") long, and 2 cm (¾") dia.	24	Each	359.75	8634		
7	Providing and fixing looking glass 55x40 cm (22"x16") size,and 5 mm thick, first quality.	5	Each	387.80	1939		
8	Providing and fixing, angle iron brackets for:-i) wash hand basin and cistern	24	Each	174.15	4180		

Scanned with CamScanner

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
	NS ITEMS						
1	Providing and fixing of mixer washel (chand washel)	30	Each	280.00	8400		
2	Providing and fixing of head and spindle of Master or equivalent complete in all respect as approved by engineer incharge.	115	Each	520.00	59800		
3	Providing and fixing Muslim shower approved brand (Master/Sonex/or equlant) I/c 1 meter long PVC flexible pipe with connections complete in all respect as approved by engineer incharge.	46	Each	640.00	29440		
	Total				**1406169**		
	Add 16% PRA				**224987**		
	G.Total				**1631156**		
	Credit of Old Material				**30955**		
	Net Total				**1600201**		

Note : (i) B.O.Q is based on rates for 2nd Bi-annual 2019 i.e. from July Ist, 2019 to December 31st, 2019 (District D.G.Khan)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2019 i.e. from July Ist, 2019 to December 31st, 2019 shall be followed.

Rate quoted by the contractor _____ % Above/ Below on above BOQ rates(s).

Quantity Surveyor
PDS-CEA Lahore

Chief Quantity Evaluator
PDS-CEA Lahore

Assistant Manager Engg.
PDS-CEA Lahore

General Manager Engg.
PDS-CEA Lahore

Scanned with CamScanner