SPECIAL REPAIR TO TOILET BLOCK OF HOSTELS AT DAANISH SCHOOL GIRLS D.G.KHAN

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
1	Dismantling glazed or encaustic tiles etc.,	2096	%Sft	1659	34773		
2	Dismantling cement concrete plain 1:4:8	524	%Cft	4001.7	20969		
3	Dismantling cement concrete with brick agreegate	692	%Cft	2182.75	15105		
4	Providing and fitting glazed earthen ware water closet squatter type (Orisa Pattern) combined with footrest. White	6	Each	1286.4	7718		
5	Providing and fitting glazed earthen ware water closet European type excluding seat and cover white (Labour Charges only)	12	Each	518.75	6225		
6	Providing and fitting P Trap 4" glazed	18	Each	153.9	2770		
7	Providing laying watering and ramming brick ballst 1 1/2" to 2" guage mixed with 25% sand for floor foundation complete in all respect	692	%Cft	4564.3	31585		
8	Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone agreegate ratio 1:2:4	524	%Cft	21921.75	114870		
9	Laying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.	2096	%Sft	15497.1	324819		
10	Distempering old surface two coat	1362	%Sft	438.3	5970		
11	White washing new surface three coat	2096	%Sft	294.4	6171		
	Total - A				**570975**		

2/2/21

Principal
Daanish School Girls
D.G.Khan

Scanned with CamScanner

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
	NON-SCHEDULED ITEM						
1	Providing lying cutting jointing testing uPVC sewerage drainage and vent pipe confirm to ISO 3633-1991 including uPVC drainage fittings with cement jointing including cost of clumping to walls suppport cutting through walls and providing sleves through concrete slabs / beams (if any) for pipe line and pipe fitting of the following dia complete in all respect i/c specials (4" dia waste)						
i	3" dia	300	PRft	165	49500		
ii	4" dia	480	PRft	240	115200		
	Total - B				**164700** ✓		
				Total (A+B)	**735675** ✓		
				Add 16% PRA	**117708** ✓		
				G.Total	**853383**		
				Say	**0.853 (M)** ✓		

Note (i) B.O.Q is based on rates for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 (District D.G.Khan)
(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2020 i.e. from July Ist, 2019 to December 31st, 2020 District D.G.Khan shall be followed.

Quantity Surveyor
PDS-CEA Lahore

Chief Quantity Evaluator
PDS-CEA Lahore

26/1/2021
Deputy Manager Engg.
PDS-CEA Lahore

General Manager Engg.
PDS-CEA Lahore

Scanned with CamScanner

SPECIAL REPAIR TO SEWER LINE AT DAANISH SCHOOL GIRLS D.G.KHAN

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
1	Earth work excavation in open cutting for sewers and manholes as shown in drawings including shuttering and timbering dressing to correct section and dimensions according to emplates and levels and removing surface water in all types of soil except shingle gravel and rock 0ft to 7ft depth ordinary soil	10619	%oCft	6370.75	67651		
2	Earth work excavation in open cutting for sewers and manholes as shown in drawings including shuttering and timbering dressing to correct section and dimensions according to emplates and levels and removing surface water in all types of soil except shingle gravel and rock 7ft to 15ft depth	4747.25	%oCft	10709.95	50843		
3	Lowering of sub-soil water table by installation of tubewells along sewer line and pumping out water for excavation in open cutting below sub soil water level concreting curing laying and jointing pipes filling haunches, etc till the completion of sewer line including disposal of pumped out water 0-4	170	PRft	1686.95	286782		
4	Providing and laying RCC pipe moulded with cement concrete 1:1 /2:3 with spigot socket or collar joint etc including cost of reinforcement conforming to BS 5911 part I 1981 class L including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade jointing cutting pipes where necessary finishing and testing etc complete 12" dia	170	PRft	432.4	73508		
5	Dry rammed brick or stone ballast 1 1/2" to 2" guage	416.145	%Cft	4114.45	17122		
6	Rehandling of earth work lead upto single through of kassi	13593.2	%oCft	1818.95	24725		
8	Cement concrete brick or stone ballast 1 1/2" to 2" guage (Ratio 1:4:8)	41.26	%Cft	12973.8	5353		
9	Pacca brick work in 1:5 other than building upto 10' height	251.445	%Cft	21182.45	53262		
10	Cement plaster 1:4 upto 20' height 1/2" thick	606	%Sft	2105.7	12761		

2/2/24
Principal
Daanish School Girls
D.G.Khan

Scanned with CamScanner

S#	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	
						Rate	Amount
11	Providing and fixing 6" thick RCC manhole cover with tee shaped C.I. frame of 22" i/d (frame weighing 37.324 kg or one maund as per standard drawing STD/PD No. 6 of 1977 complete in all respect.	2	Each	8932.55	17865		
12	Providing and fixing 1 1/4"x1 1/4"x3/16" angle iron step in manhole chambers, including carriage and setting the same in work to correct lines and level	16	Each	336.2	5379		
13	Cement concrete 1:2:4 plain i/c placing compacting curring etc complete	17.96	%Cft	21921.75	3937		
14	Extra for making finishing benching floor work in manhole chamber, with 1/8" thick cement finish	26	%Sft	1860.65	484		
				Total	**619672**		
				Add 16% PRA	**99147**		
				G.Total	**718819**		
				Say	**0.718 (M)**		

Note (i) B.O.Q is based on rates for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 (District D.G.Khan)
(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2020 i.e. from July Ist, 2019 to December 31st, 2020 District D.G.Khan shall be followed.

Quantity Surveyor
PDS-CEA Lahore

Chief Quantity Evaluator
PDS-CEA Lahore

26/11/2021
Deputy Manager Engg.
PDS-CEA Lahore

General Manager Engg.
PDS-CEA Lahore

Scanned with CamScanner

SPECIAL REPAIR TO MESS COOKING AREA AT DAANISH SCHOOL GIRLS DERA GHAZI KHAN

DNIT/ B.O.Q

Sr. No.	Description	Qty	Unit	Rate	Amount	Rate to be quoted by the contractor	Amount
						Rate	
A	**STANDARDIZED ITEMS**						
1	Dismantling glazed or encaustic tiles, etc	2846	%Sft	1659	47215		
2	Laying floor of approved white glazed tiles 1/4" (6mm) thick in white cement 1:2 over 3/4" (20mm) thick cement mortar 1:2, complete	2846	%Sft	15497.10	441047		
	Total - A				**488262**		
	Add 16% PRA tax				**78122**		
	Grand Total				**566384**		
	Say Rs.				**0.566 (M)**		

Note : (i) B.O.Q is based on rates for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 (District Dera Ghazi Khan)

(ii) In case of any ambiguity regarding rate, MRS/ Input rates of Finance Department displayed on web-site for 2nd Bi-annual 2020 i.e. from July Ist, 2020 to December 31st, 2020 District Dera Ghazi khan shall be followed.

Principal
Daanish School Girl
D.G.Khan

Quantity Surveyor
PDS-CEA Lahore

Chief Quantity Evaluator
PDS-CEA Lahore

26/11/2021

Deputy Manager (Engg)
PDS-CEA Lahore

General Manager (Engg)
PDS-CEA Lahore

Scanned with CamScanner